BANGALORE DIVISION.

ADVERTISEMENT.

The 5th March 1892.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 17th March 1892 for restoring the Hulikal Tammanhalli Tank, [illegible]gistered No. 214, Magadi Taluk. An approximate estimate of quantities is given below. These [illegible]ntities are not guaranteed. The work should be completed by the end of November 1892.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Hulikal Tammanhalli Tank, Registered No. 214, Magadi Taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed estimate of the probable cost of restoring the Hulikal Tammanhalli Tank, Registered No. 214, Magadi Taluk.

Items of Work.	Per.	Quantity.
Bund—		
Earthwork	C. Yd.	34,800
New stone revetment	do	4,332
Old Do	do	3,000
Grade stones	No.	52
B. M. stones	do	2
Register No. Stone	do	1
Gauge stone dressed	do	1
Left waste weir—		
Earthwork	C. Yd.	3,040
Brick in chunam	C. Ft.	3,203
Slab stones	Sq. Ft.	788
Rough stone sujikat	C. Yd.	1,208
Rough stone work for wings..	do	94
Plastering with chunam	Sq.	10
Date stone	No.	1
Repairing No. 1 and 4 sluices	L. S.	2

R. T. SCALDWELL,
Executive Engineer.

HASSAN DIVISION.

ADVERTISEMENT.

The 17th February 1892.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer Hassan Division, up to 20th March 1892, for constructing a Munsiff's Court at Hole-Narsipur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1893.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at H[illegible]san between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200—0—0 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing a Munsiff's Court at Hole-Narsipur;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.